



## Solicitation Solicitation Amendment

Date

1. Amendment Number A04 to Solicitation Number 123125-08-A-0204

09/09/2008

2a. Facility  
DAWSONVILLE, GA - MAIN OFFICE

2b. Project H33504  
Building Expansion

3a. Offeror Name and Address

3b. Issued By  
Southeast FSO  
1735 N Brown Rd Ste 200  
Lawrenceville, GA 30043-8153

3c. Contact MARK T LONGFELLOW  
678-442-6041

4. The above numbered solicitation is amended as set forth in Block 5.

Note: Offerors must acknowledge receipt of this amendment prior to the date and time specified in the solicitation by one of the following methods:

- By signing and returning one copy of the amendment;
- By acknowledging receipt of this amendment on each copy of the offer submitted; or
- By submitting a separate letter or telegram which includes a reference to the solicitation and amendment numbers.

FAILURE OF YOUR ACKNOWLEDGMENT TO BE RECEIVED AT THE PLACE SPECIFIED IN THE SOLICITATION PRIOR TO THE DATE AND TIME SPECIFIED FOR RECEIPT OF OFFERS MAY RESULT IN REJECTION OF YOUR OFFER.

If by virtue of this amendment, you desire to change an offer already submitted, such change may be made by telegram or letter provided such telegram or letter makes reference to the solicitation and amendment numbers, and is received prior to the date and time specified.

The date and time specified for receipt of offers is:

09/18/2008 03:00 PM

5. Description of Amendment:

THE SOLICITATION NUMBER ON THIS PROJECT HAD TO BE CHANGED TO 123125-08-A-0204.

The purpose of this Amendment A04 to Solicitation No. 123125-08-A-0204 is to revise/clarify/delete items on attached.

These items are incorporated and made a part of this solicitation.

All other items will remain the same.

6. Contractor Signature

Date Signed

U. S. Postal Service Signature

Date Signed

Name of person authorized to sign

Contracting Officer  
MARTIN R PETREY



**Facilities Department  
Attachment to Amendment**

1. Amendment Number A04 to Solicitation Number 123125-08-A-0204

- 01 Revisions/deletions/clarification - 1 page
- 02 Drawing C1.2 - Civil Grading & Drainage Plan
- 03 Drawing E1.1 - Electrical Power Plan
- 04 Drawing E1.3 - Electrical Site Plan

Drawing

- C1.1** A. Delete all landscaping. Only work as required under erosion control to be included.  
B. Delete monument sign.
- C1.1.A** A. Clarification: The concrete demolition is limited to the existing curbs at the northeast corner of the carrier parking and the existing transformer and condenser unit pads.
- C1.2** A. Detention Pond, storm water pipe, and related structures deleted.  
B. Grade on the north side of the expansion raised to a minimum elevation of 1377.  
C. 6" rain water collector pipe added to discharge on new concrete paving. See revised Drawing C.1.2 attached.
- C1.3** A. Delete erosion control on east side of site.
- C1.4** A. Delete new light poles at north side of new pavement and west side of existing parking area. Additional head to be added to existing light pole at south side of new pavement.
- A0.0** A. Delete concrete sidewalk to Inspectors office and substitute 2'x2'x2" concrete pavers at 3'-o.c. per C1.1.
- A1.2** A1 Delete Items 7, 8, 9, 10, 13, 14, and 1.  
Floor Plan. All other items to remain and be included in Base Bid.  
A2 Delete Items 7, 10, 11, 12, and 13.  
Ceiling Plan. All other items to remain and be included in Base Bid.
- A1.1** A. Reduce number of window Type 1 from 12 to 8.  
B. Delete items 1, 2, and 5.  
All other items to remain and be included in Base Bid.
- A1.2** A. Delete Items 1, 2, 5, 6, 9, and 10.  
All other items to remain and be included in Base Bid.
- A1.3** A. Delete Items 1, 6, 7, 8, and 9.  
All other items to remain and be included in Base Bid.  
B. Reduce number of fixtures in P.O. Box Lobby from 18 to 14.
- A1.4** A. Delete 1-1/2" rigid insulation from roof deck.
- M1.2** Clarification:  
A. Replacement of FCU-1 A, FCU-1B, CU-1A, and CU-1B to form Add Alternate 5.1.
- M.1.3** A. Delete VF-1 and thermostat.  
B. Existing FCU-1, FCU-1B, CU-1A, and CU-1B to form Add Alternate 5.
- E1.1** A. Riser Diagram and location of meter and disconnects revised. See revised Drawings E1.1 & E1.3 attached.  
B. VF-1 Deleted.
- E1.2** A. Fixtures R-4 in P.O. Box Lobby reduced from 18 to 14 and together with all fixtures in the Customer Lobby to be included in Base Bid.

**END OF ADDENDUM**